DEPARTMENT OF THE ARMY CESPK PAM 1110-1-5

Sacramento District, Corps of Engineers 650 Capitol Mall

CESPK-CO Sacramento, California 95814-4794

PAMPHLET NUMBER 1110-1-5

1 May 1991

PCB MANAGEMENT PROGRAM MANUAL AND GUIDE

1. Purpose: The purpose of this manual is to set forth the procedures required during the design and construction of projects that have (or may

have) items of electrical equipment that contain polychlorinated biphenyls

(PCBs). The guides contained herein provide information necessary to generate

project specification requirements based upon different PCB conditions.

2. Applicability. This pamphlet applies to all elements of the Sacramento

District involved in the management, design, construction, or operation of

projects that have, or may have, items of electrical equipment that contain PCBs.

3. References: Code of Federal Regulations (40 CFR 761).

LAURENCE R. SADOFF COL, EN Commanding

PCB MANAGEMENT PROGRAM MANUAL and GUIDE

1. General.

This publication prescribes the general procedures and instructions in identifying, handling and disposal of polychlorinated biphenyls (PCBs). This guide does not preempt the Code of Federal Regulations (40 CFR 761) or other more stringent Federal or local statutes and regulations. It is prudent to consult the latest Federal, State and local government requirements in the handling of PCBs. If further clarification or references are needed, the 40 CFR 761 should be consulted (located in CESPK-OC.)

2. PCB characteristics.

a. Background.

The term polychlorinated biphenyls designates a group of 209 chlorinated organic compounds introduced in 1929 by Swann Chemicals. Chemicals was purchased by the Monsanto Company in 1935. In October, Monsanto Chemical Company, the sole producer, voluntarily ceased production of PCBs. There are dozens of trade names used for PCB products (see attachment #1), the most common are Aroclor, Inerteen and Pyranol. In the electrical industry, PCBs are often collectively referred to as "Askarels". PCBs been extensively used in large high/low voltage capacitors, transformers, oil circuit breakers, reclosers, high intensity discharge lamp ballasts, fluorescent ballasts, oil switches and sectionalizers. Other industrial of PCBs include fluids for heat transfer equipment and hydraulic systems, gas turbines, and vacuum pumps, fire retardants, plasticizers in adhesive textiles, surface coatings, sealants, and in inks for printing and carbonless

The manufacture, processing, and distribution of PCBs at concentrations of 50 parts per million (ppm) or greater and PCB items with concentrations of 500 ppm or greater present unreasonable risks to

health and

copy paper.

the environment.

Experimental tests on animals indicate that PCBs can have adverse ecological and toxicological effects. It has been shown that PCBs, like mercury and arsenic, tend to accumulate to levels harmful to living organisms.

The adverse physiological effects of PCBs on living organisms and $% \left(1\right) =\left(1\right) +\left(1\right) +$

their tendency towards bioaccumulation resulted in enactment of the Toxic

Substances Control Act (TSCA) of 1976 and EPA establishment of 40 CFR 761.

40 CFR part 761 establishes prohibitions and requirements for the

manufacturing, processing, distribution in commerce, use, disposal, storage,

and the marking of PCBs and PCB items. TSCA called for a ban on the use,

manufacture, and distribution of PCBs by 1980, except for totally enclosed,

authorized, or exempted uses granted by Environmental Protection Agency (EPA).

b. Characteristics of PCBs.

Askarel is the most common name used in the electrical industry to describe a class of nonflammable, synthetic, chlorinated, hydrocarbon insulating liquid. It is composed of PCBs mixed with chlorobenzenes to produce different blends for electrical manufacturers.

General characteristics of askarel:

- (1) Heavier than water.
- (2) Higher dielectric strength than mineral oil.
- (3) Nonflammable.
- (4) Nonexplosive.
- (5) Not susceptible to deterioration by oxidation.
- (6) Lower coefficient of expansion than mineral oil.
- (7) Will dissolve some insulating materials and paints.
- $\ensuremath{\text{(8)}}$ At normal temperatures, viscosity is almost like mineral oil.
- $\ensuremath{\mbox{(9)}}$ Dielectric strength is reduced with presence of moisture.

c. Analysis of substances.

 $\hbox{ Electrical equipment containing PCB insulating oils must be identified }$

and appropriate actions taken to comply with 40 CFR 761. The identification

process includes the taking of oil samples and submitting them to an analytical laboratory for identification and determination of concentration

levels. Where electrical equipment is not marked or the type of

insulating

oil is not known, the equipment should be treated as if it is PCB contaminated and handled with similar precautions.

As with many organic chemical solvents, skin irritations may occur as

a result of prolonged exposure. The following precautions are to be followed

when handling askarel:

- (1) Skin contact with the oil is to be avoided. Utilize neoprene gloves, sleeve guards, aprons, neoprene boots, eye goggles, or face shield.
- (2) Heating of askarel is prohibited unless the system is entirely enclosed and vapor contact is controlled so there is no exposure to workers.

Samples of electrical insulating oils shall be obtained by the $\operatorname{methods}$

described in ASTM D 923-88, or other methods as mentioned by the ASTM. Testing for PCBs shall be as described by ASTM D 3304-77, and D 4059. Identification and classification of concentration requires the utmost in $\frac{1}{2}$

cleanliness and handling of the samples. Procedures outlined in the $\ensuremath{\mathsf{ASTM}}$ test

procedures should be adhered to, not only for accuracy, but also to $\mbox{maintain}$

a consistency in procedures should there be a large number of samples to be obtained.

d. Responsibilities.

The customer (generator of PCBs) shall determine the method of disposal, or have that duty designated to another responsible authority. The

responsibility of disposal, until documents of final destruction are received,

rests entirely upon the generator of the PCB! The generator's responsibility

is not relinquished by delegation of duties or with the issuance of a disposal contract.

3. PCB Procedures for Projects.

a. Predesign conference.

On or before the predesign conference, the USACE Project Manager (PM),

shall coordinate with the customer and determine if there are any items suspected of being PCB contaminated equipment, or PCB equipment (see definitions, attachment #2). If PCB is non-existent, it has to be indicated

in the PM's pre-design conference minutes and no other PM action regarding

PCBs is required. The designer (A-E or Inhouse) will then indicate in the

design analysis that there are no PCBs in the project. If there is any suspect PCB contaminated equipment, the PM shall ask the customer what

type of

services will be required to be performed by the A-E (to provide service to

identify PCBs) and the construction contractor for PCB items including $\tt method$

of disposal. The agreed upon procedures for the PCB items shall be documented

in a "Memorandum of Understanding". This Memorandum of Understanding shall be

made part of the design analysis and made part of "Special Construction Concerns" forwarded to the Area/Resident Engineer.

b. Procedures for projects with PCBs.

The PM and the customer shall determine what needs to be done regarding the handling and disposal of PCB items on a project and the source

of funds for design and construction. The PM and the project designer shall $% \left(1\right) =\left(1\right) +\left(1\right)$

coordinate with the customer regarding the location(s) of items of suspect $\ensuremath{\mathsf{PCB}}$

equipment, PCB-contaminated equipment, and PCB equipment and clearly identify

them on the project's plans and specifications. The customer shall be promptly notified in writing, by the Project Manager/designer, if leaking

equipment is noticed during any site visits.

There are several combinations of efforts to be required by a construction contract for handling of PCBs on a given project. Several of the

common options are as follows:

 $\,$ (1) No PCBs on the project: If there are no PCBs within the scope of

the project or the customer will remove, take control, transport, and dispose

equipment that contains PCBs, the designer shall include a statement in the

design analysis indicating that there will be no requirement to handle PCBs

and that the customer assumes sole responsibility for removal, transport,

storage and disposal of such equipment. The installation must provide a letter stating that all PCBs have been removed and the site is clean.

(2) PCBs on the project; construction contractor to remove such

equipment from service and have the customer remove the equipment from the

jobsite: The contractor will be required to remove items suspected or known

to contain PCBs out of service using procedures that meet the requirements of

applicable regulations. After the equipment is out of service, the customer

will handle all necessary reporting and disposal requirements. Testing, manifesting, etc. will be done by the customer. It may be necessary for the

contractor to complete documentation to turn over the equipment to the customer. These requirements shall be determined and reflected in the

final

bidding documents. A Memorandum of Understanding regarding this matter must

be signed by the Project Manager and a representative of the customer. The

memorandum must indicate that the equipment will be transported off the project site as soon as possible and no later than 48 hours after removal from

service. PCB contaminated equipment, PCB equipment and suspect PCB equipment

can only be stored temporarily for up to 30 days and stored for disposal for $\ensuremath{\text{0}}$

up to 1 year. These are LEGAL REQUIREMENTS. For the purposes of this quide,

"removal" means "the time the equipment is disconnected from service."

(3) Construction contractor to remove, test, and transport the equipment to a location designated by the customer to a location on the Post/Base: The contractor will be required to remove items suspected or known

to contain PCBs out of service using procedures that meet the requirements of

applicable regulations. After the equipment is out of service, the contractor

must test the fluid in the equipment to determine the concentration of PCBs

within that equipment. The testing will be accomplished according to the

appropriate ASTM test sampling and analysis methods. The customer must make

any special requirements for testing or manifesting (amount of PCBs in each

item of equipment, etc.) known and those requirements must be stated in the bidding documents. After testing, the contractor will be required to

transport the item(s) of PCB-containing equipment to a location designated by

the customer. This location must be clearly identified in the bidding documents. The customer will handle all necessary manifesting, reporting, and

disposal requirements once the equipment has been turned over to the customer.

It may be necessary for the contractor to complete documentation to turn over

the equipment to the customer. These requirements need to be determined and

reflected in the final bidding documents. A memorandum of understanding regarding this matter must be signed by the Project Manager and a representative of the customer.

(4) Construction contractor to remove, test, and dispose of the equipment off of the Post/Base: The contractor will be required to remove

items suspected or known to contain PCBs out of service using procedures that

meet the requirements of applicable regulations. After the equipment is out

of service, the contractor must test the fluid in the equipment to determine

the concentration of PCBs within that equipment. The testing will be

required

to be according to the appropriate ASTM test sampling and analysis methods.

After testing, the contractor will be required to transport the item(s) of

PCB-containing equipment to a location off of the installation in accordance

with all applicable regulations. The contractor shall also comply with the

requirements described under "Manifest Requirements" and "Qualifications of

Disposal Facility."

4. Bid Document Requirements.

The bid documents (plans and specifications) must clearly delineate the

work that will be required to be performed for handling and disposing PCBs on

a project. The plans must indicate the type of equipment, KVA, phase, voltage

(primary and secondary, when applicable), equipment manufacturer, number of

gallons of fluid or solid PCB, and any other pertinent information. The fact

that regulations may require that certain procedures be followed is not alone

sufficient for bidding purposes; statements within the specifications are

necessary to require the contractor to comply with the applicable regulations

(by accurate citation). Wherever possible, a description of the actual work

required to be performed must be stated to preclude misunderstandings and $% \left(1\right) =\left(1\right) +\left(1\right) +$

claims during construction.

Following are recommended specification statements to be used as a guide

for project specifications. Beware that regulations change and that these

requirements must be verified by the designer/PM/customer for each project.

The text of the regulations serving as the genesis for the stated requirements

are reproduced here in small type for reference and information but are not

intended to be literally a part of any final project specification.

a. PCB Testing.

The contractor shall submit a certificate of qualification of

testing laboratory for government approval. A certified copy of qualifications shall be submitted to the government for approval no later than

30 days before the schedule date of removal of the equipment.

Contract-required testing shall be performed no later than 48 hours

after removal from service of each item of equipment. Delay of testing for

the purpose of group sampling (i.e. waiting for removal of other equipment) is

not acceptable. The PCB test shall be per ASTM 3304-77 (Reapproved 1983)

"Standard Method for Analysis of Environmental Materials for Polychlorinated

Biphenyls" for air, water, soils, and sediments or per ASTM D 4059-86 "Standard Method for Analysis of Polychlorinated Biphenyls in Insulating Liquids by Gas Chromatography," for electrical insulating liquids. Samples

for laboratory testing shall be per ASTM D 923-86 "Standard Methods of Sampling Electrical Insulating Liquids."

No other testing method shall be performed without the written approval of the Contracting Officer and EPA. Other testing methods not approved by the Contracting Officer and EPA will be considered as "not meeting

the contract requirements" and be rendered unacceptable.

Results of the testing shall be available within 30 calendar days

after removal. The result of the test shall be marked on each individual $\ensuremath{\mathsf{PCB}}$

equipment. Three copies of each test result shall be provided to the Contracting Officer as soon as the results of the tests are available.

 $\label{eq:when the tests} \mbox{ are completed, the sample shall be disposed of properly}$

per 40 CFR 761.65 (i) (4).

--*-*-*-*-*-*-*-*-*-

STORAGE, DISPOSAL AND HANDLING

The disposal of PCB-contaminated electrical equipment (with the liquids drained), solids (such as soil, rags and debris), or liquids other than mineral oil dielectric fluids which contain PCBs greater than 50 but less

than 500 ppm (parts per million) shall be disposed of by:

- 1. Approved incinerator which complies with section 761.70.
- 2. Chemical waste landfill which complies with section 761.75.

Storage areas, prior to disposal, shall comply with section 761.40. The PCB

articles and $% \left(1\right) =\left(1\right) +\left(1\right) =\left(1\right) +\left(1\right$

days. A Spill Prevention Control and Countermeasure (SPCC) Plan as described

in Part 112, section 761.65 shall be prepared and implemented.

The disposal of PCB containers with PCB concentrations 500 ppm or greater, shall be disposed of by:

- 1. Incineration which complies with section 761.70.
- 2. Chemical waste landfill that complies with section 761.75, provided that the container must first be drained of the liquid PCBs,

and the

liquid disposed of in accordance with paragraph a of section 761.60.

consisting of capacitors, properly drained transformers, contaminated soil,

dirt, rags, asphalt, properly drained containers, and other debris is published in the Federal Register. For further information on the EPA approval of disposal facilities, contact the appropriate EPA Regional Office.

The method of disposal (either by contract or by government) is dependent upon

many varia-bles. The size of the item, quantities of items and/or volume of

liquid, time constraints, permits, and availability of transportation. Whichever method is selected, by contractor or by government, legal responsibility for the disposal of the PCBs is the sole responsibility of the

"generator" or original owner of the PCBs. Contracting for removal does not

relieve the "generator" of the legal responsibility, but it places the liability of any accidental spill and clean-up upon the contractor. Therefore, selection of a disposal contractor should be based upon past record, performance, and reputation.

--*-*-*-*-*-*-*-*

b. PCB Transportation.

Equipment containing PCBs shall be transported to [building #, Post/Base location] [temporary storage site as indicated] [off-site storage/off-site disposal location]. Transport of such equipment shall be per

CFR 40 CFR 761, U.S. Department of Transportation (DOT) hazardous materials

regulations (49 CFR 171-177), and DOT motor carrier regulations (49 CFR 391).

 $\label{tensor} \mbox{Transport of laboratory sample(s) for testing and after testing shall}$

comply with 49 CFR 173.345 and U.S. Postal Regulations 652.2 and 652.3. The

sample shall include the following information:

- (1) The sample collector's name mailing address, and telephone number
- (2) The laboratory's name, mailing address, and telephone number $\boldsymbol{\theta}$
 - (3) The quantity of the sample
 - (4) The date of shipment
 - (5) A description of the sample.

The sample shall be packaged so it will not leak, spill or vaporize from its packaging.

Untested equipment shall be treated and handled as PCB-contaminated.

Each transport vehicle shall be marked (see Fig 1) as if loaded with PCB containers, if the cargo contains more than 45 kg (99.4 lbs.) of PCBs in the

liquid stage or with one or more PCB Transformers. Transport vehicles loaded

with PCB items that contain more than 45 kg of liquid PCBs in concentrations

of 50 ppm to 500 ppm shall be marked. Transport of PCBs equal to or greater

than 4.5 kg and equal to or greater than 200 ppm shall be accompanied by ${\tt DOT}$

approved shipping papers (49 CFR 172, Subpart C). The shipping paper shall be

with the driver during transport and preferably kept with the driver's side

door container. The Contracting Officer, or his authorized representative,

shall be provided a copy of the shipping papers not later than 10 working

days before transport. The contractor shall make the necessary arrangement to

the off-site storer or off-site disposer for the exact day of arrival of the

PCB waste. If the PCB waste cannot be delivered, the contractor shall return ${\bf PCB}$

the PCB waste to the Post/Base and redeliver as soon as possible at no extra $\,$

cost to the government.

The carrier utilized for transportation of the PCB item(s) shall be experienced with the transportation of PCB item(s), and contractor shall show proof of transporter liability and capacity to provide adequate and

rapid

clean up of spills occurring during handling and transporting.

Contractor shall submit copies of the transporters "Bill of Lading"

accompanied by proper state, federal and local permits prior to transporting

within 30 days upon receipt of permission to ship PCB item(s). Phone numbers,

address and names of responsible parties involved shall be provided for all

aspects of the transporting and disposal.

c. Transfer of item(s) of equipment to the customer.

Non-PCB equipment, suspect PCB equipment, PCB contaminated equipment,

and PCB equipment shall be transported and turned in to the customer at the

location indicated. [A completed DA Form 3161 Request for Issue or Turn-in

shall be submitted to the customer together with the results of the

laboratory

analysis during equipment(s) turn in. Contractor shall provide the Contracting Officer, or his duly appointed representative, a copy of completed DA

Form 3161 and the results of the laboratory test.]

--*-*-*-*-*-*-*-*-*-*-

 $\ensuremath{\operatorname{NOTE}}\colon$ A description of any forms, etc. that the contractor must complete as

part of the turn-in procedure must be provided in the above paragraph. The

bracketed information may be insufficient for many installations.

LABELING AND MARKINGS

Each of the following items shall be marked (Fig. 1) unless the PCB item is

too small to $% \left(1\right) =\left(1\right) +\left(1\right$

6-inches on each side. If the equipment is too small for this mark, the

small mark (Fig. 2) may be used. The small mark which is 1 by 2-inches, may

be reduced to a minimum 0.4 by 0.8-inches.

- 1. PCB containers.
- 2. PCB transformers.
- Equipment containing a PCB transformer or a PCB large highvoltage capacitor.
 - 4. PCB large low-voltage capacitor.
 - 5. Electric motor using PCB coolant.
 - 6. Hydraulic systems using PCB hydraulic fluid.
- 7. Heat transfer systems (other than PCB transformers) using PCBs.
- $\,$ 8. PCB article containers containing articles or equipment that $\,$ must

be marked under the provisions above.

- 9. Each storage area used to store PCBs and PCB items for disposal.
- 10. Each transportation vehicle shall be marked on each side and end if

it is loaded with PCB containers that contain more than 99 pounds of PCBs in $\,$

the liquid phase or one or more PCB transformers.

In addition to the requirement above, transformer locations shall also have

markings (fig 1) on the vault door, machinery room door, fence, hallway, or

means of access, other than grates and manhole covers to a PCB transformer.

The mark must be placed in locations, in a $% \left(1\right) =\left(1\right) +\left(1\right)$

emergency response personnel fighting a fire involving this equipment.

In areas where the PCB items are fenced off to unauthorized personnel,

such as

outside capacitor and transformer locations, a mark shall be placed on the

fence and gate on all exterior sides.

--*-*-*-*-*-*-*

d. Marking of PCB equipment.

Marking of PCB equipment, if not already marked, shall be done

time of removal from use. Items of PCB equipment shall be marked no later

than 48 hours after the receipt of the laboratory results. [Electric motors

using PCB coolants], [hydraulic systems using PCB hydraulic fluid], [heat

transfer systems (other than PCB Transformers)] containing PCBs in concentration of 50 ppm to 500 ppm, and PCB Containers with more than 45 kg of

liquid PCBs in concentration of $50~\rm{ppm}$ to $500~\rm{ppm}$ shall be marked. Confusing

or conflicting PCB markings shall be removed or painted over before new marking is performed. Marking shall also be placed in a position on the exterior of the PCB items or transport vehicles so that the marks can be easily read by any persons inspecting or servicing the marked PCB items or

vehicles. Marking formats shall be per 40 CFR 761.45. See Figure 1 and Figure 2.

e. Storage for disposal.

[Contractor provided] storage facilities shall comply with 40 CFR

761.65. Contractor shall submit plans and specifications for government and

EPA approval. Any PCB equipment and PCB containers shall be removed from

storage site within one year from the date when it was first placed into storage. The storage facility shall be marked per 40 CFR 760.40(a)(10). Any

tool or equipment that has become contaminated with PCBs shall not be removed

from the storage facility area unless it has been decontaminated as specified

in 40 CFR 761.79. All PCB equipment or containers in storage shall be inspected for leaks at least once a month. Temporary storage shall be per 40

CFR 761.65(c)(1). Capacitors and equipment temporarily stored outside shall

be checked for leaks weekly. A maximum of 30 days is allowed for temporary

storage. Containers for storing PCB shall comply with 40 CFR 761.65(c) (iv)(6)

or 29 CFR 1910.106. Contractor shall prepare and implement a Spill Prevention

Control and Countermeasure plan (SPCC) when using containers designed, constructed and operated in compliance with Occupational Safety and Health

Standards (OSHA) 29 CFR 1910.106. All PCB articles and PCB containers shall

be dated on the articles when they are placed in storage, and should be managed so they can be located by the date they are put in storage. A record

of the date and quantity added from a batch container shall be $\mbox{maintained}$.

The record shall include the date, quantity, and disposition of any batch of

PCBs removed from the container. Contractor shall establish and maintain records per 40 CFR 761.180. A current copy of the record shall be kept in

the storage facility. Current records shall be made available to the government no later than $48\ \mathrm{hours}$ after request.

Any leaking PCB articles and their contents shall be transferred

materials and residues shall be disposed of in accordance with 40 CFR $761.60\,(a)\,(4)\,.$

f. Spill response.

Contractor shall provide a ready crew for spill response. The ready

crew shall respond as soon as possible and in no case later than 24 hours

after discovery of PCB spill. A spill constitutes an illegal disposal and

must be thoroughly and rapidly cleaned up.

PCB spill clean up shall be per 40 CFR 761.125. The Contracting Officer, or authorized representative, shall be notified if a spill has occurred as soon as possible and in no case later than 24 hours after discovery. U.S. National Response Center (NRC), telephone number 1-800-424-8802 (24 hours) shall be notified for any PCB spill that is 4.54 kg

(10 lbs.) or more with concentration of 50 ppm or more. Other reporting requirements shall per 40 CFR 761.125 (a)(i) through (a)(iv). Disposal of

clean-up debris shall be in accordance with the provisions of 40 CFR 761.60.

At the completion of the clean up the contractor shall document the clean up

with records and certification of decontamination. Information on the records

and certifications shall be per 40 CFR 760.125. The contractor shall provide

the contracting officer, or authorized representative, with a copy of the

records and certifications. The records and certifications shall be maintained for five years. The clean up of the spill, records and certifications, transportation, and disposal of spill debris shall be at no

extra cost to the government.

g. Manifest requirements.

Contractor shall prepare a manifest on EPA Form 8700-22 and a continuation sheet when necessary, for PCB waste stored off-site or disposed

off-site. The contractor shall provide the information per 40 CFR 761.207

(a) (1) through (a) (3) and (g). When the state to which the shipment is manifested (consigned) to supplies and requires the manifest, the contractor ${\bf r}$

shall use that state's manifest. When the state to which the shipment is

manifested does not supply the manifest, the contractor shall use the state's

manifest where the shipment is originated. If neither state supplies the

manifest, the contractor may obtain the manifest from any source. Manifest is

required for PCB waste that is subject to the disposal requirement of 40 CFR

761.60 including waste with PCB concentration below 50 ppm as a result of

dilution. An example is spill cleanup material containing less than 50 ppm

used for spill clean up that involves material containing 50 ppm or greater.

A copy of the manifest shall be submitted to the Contracting Officer prior to

shipment. The manifest shall be with the driver of the transport vehicle and

shall accompany the PCB waste at all times during transport. A legible copy

shall be furnished to the operator of the disposal site and an additional

copy to be returned to the contracting officer by the owner of the storage or

disposal site. The owner of the storage or disposal site shall indicate that

the shipment indicated in the manifest has been received.

h. Qualifications of disposal facility.

The disposal facility shall be an EPA approved facility. A copy of

the current written certificate or letter of approval from EPA shall be submitted by the contractor for government approval. No disposal shall be

initiated without the written approval of the contracting officer. The contractor shall make sure that the disposal facility will have a current EPA

approval at the time of disposal. Disposal shall be per 40 CFR 761.60.

RECORD KEEPING AND FILE MANAGEMENT

Records on the disposition of PCBs and PCB items are required by the $\ensuremath{\mathtt{EPA}}$ for

each facility using or storing(at one time) 99.4 pounds of PCBs contained in

PCB containers or one or more PCB transformers, or 50 or more PCB large high-

document prepared for each facility by July 1 covering the previous calender

year. Projects with one or more facilities that use or $% \left(1\right) =\left(1\right) +\left(1\right) =\left(1\right) +\left(1\right) +\left(1\right) =\left(1\right) +\left(1\right) +\left($

items in the quantities stated above may maintain the records and documents at $\ensuremath{\mathsf{T}}$

a facility that is normally occupied for 8-hours a day, provided the identity

of this facility is available at each facility using or storing PCBs and PCB

items. The $% \left(1\right) =\left(1\right)$ records and documents shall be maintained for at least 5 years

after the facility ceases using or storing PCBs and PCB items. The records $\,$

following information for each facility included in the annual document:

- 1. Total weight of any PCBs and PCB items in PCB containers, including the identification of container contents, such as liquids and capacitors.
 - 2. Total number of PCB transformers and total weight of any

PCBs

contained in the transformers.

3. Total number of PCB large(greater than 3 lbs dielectric fluid) $\,$

high- or low-voltage capacitors.

For PCBs and PCB items removed from service, the location of the initial disposal or storage facility, name of the owner or operator of the facility,

and the date on which the article or container was removed from service shall

be documented.

Total quantities of PCBs and PCB items remaining in service at the end of the calendar year using the following breakdown:

- 1. Total weight of PCBs and PCB items in PCB containers, including the identification of container contents, such as liquids and capacitors.
- $\,$ 2. Total number of PCB transformers and total weight of any PCBs contained in the transformer.
 - 3. Total number of PCB large high- or low-voltage capacitor

--*-*-*-*-*-

i. Maintenance of data and records.

Data and records shall be per 40 CFR 761.70. All data and records

required by 40 CFR 761.70 shall be maintained in accordance with 40 CFR 761.180. The contractor shall make available the records when requested by

the government no later than 7 working days after request. An itemized record

of destruction or disposal shall be submitted to the government no later

30 days after PCB destruction or disposal. The itemized record of destruction

shall include contract number of the project, project name, location and specification number. The record shall indicate where (disposal facility name

and address) the PCBs removed from this project have been disposed of, date,

principal (disposal facility owner), and telephone number, in accordance with

40 CFR 761.60.

Bibliography:

Code of Federal Regulations, Title 40, Part 761
PCB Disposal Manual, Electrical Power Research Institute (EPPRI),
SCS Engineers Inc., June 1985.
Shipboard Hazardous Material/Hazardous Waste Training Manual,
U.S. Navy, March 1984.

LIST OF PCB TRADEMARKS (PARTIAL LISTINGS)

Trade Name

Aroclor/Askarel*

Asbestol* Askarel* Askarel* Askarel*

Co.

Askarel*, EEC-18

Chlorextol
Clopen
CK
Diaclor
Dykanol
EED-18
Elemex
Fenclor
Hyvol
Inerteen
Kennechlor
No-Flamol

Non-Flammable Liquid

Phenoclor

Manufacturer

Monsanto

American Corporation Ferranti-Packard Ltd. Hevi-Duty Electric

R.C. Uptegraft Manufacturing

Niagara Transformer Co.

Allis Chalmers
Bayer (Germany)
Caffaro (Italy)
Sangamo Electric
Cornell Dubilier

Power Zone Transformer

Mcgraw Edison Caffaro (Italy)

Aerowax

Westinghouse Electric Mitsubishi (Japan) Wagnor Electric

ITE Circuit Breaker Co.

Prodelec (France)

Pyralene Pyranol Saf-T-Kuhl Santotherm Prodelec (France) General Electric Kulhman Electric Mitsubishi (Japan)

Note: * Indicates generic name of PCBs.

DEFINITIONS

PCB and PCBs - Any chemical substance that is limited to the biphenyl molecule

that has been chlorinated to varying degrees and any combination of substances

which contains such substance.

Manifest - The shipping document EPA Form 8700-22 and any continuation sheet

attached to EPA form 8700-22

PCB Article - Any manufactured article, other than a PCB Container, that contains PCBs and whose surface(s) has been in direct contact with PCBs.

PCB Article Container - means any package, can, bottle, bag, barrel, drum.

tank, or other device used to contain PCB Articles or PCB Equipment, and whose

surface(s) has not been in direct contact with PCBs.

PCB Container - Any package, can, bottle, bag, drum, barrel, drum, tank, or

other device that contains PCBs or PCB Articles and whose $\operatorname{surface}(s)$ has been

in direct contact with PCBs.

PCB Equipment - Any manufactured item, other than a PCB Container or a PCB

Article Container, which contains a PCB Article or other PCB Equipment, and

includes microwave ovens, electronic equipment, and fluorescent light ballasts $% \left(1\right) =\left(1\right) \left(1\right) \left($

and fixtures.

PCB Item - Any PCB Article, PCB Article container, PCB Container, or PCB Equipment, that deliberately or unintentionally contains or has a part of it

any PCB or PCBs.

PCB Transformer - Any transformer that contains 500 ppm PCB or greater.

PCB-Contaminated Electrical Equipment - Any electrical equipment, including

but not limited to transformers (including those used in railway locomotives

and self propelled cars), capacitors, circuit breakers, reclosers, voltage

regulators, switches (including sectionalizers and motor starters), electromagnets, and cable, that contain 50 ppm or greater PCB, but less than

500 ppm. Oil-filled electrical equipment other than circuit breakers,

reclosers, and cables whose PCB concentration is unknown must be assumed to be

PCB-Contaminated Electrical Equipment.

PCB waste(s) - those PCBs and PCB Items that are subject to the disposal requirement of 40 CFR s 761.